

Schedule of Quantity for: **“Repairing of Bituminous road at Turamdih Township”**

**(Re-Tender) to N. I. T No.: TMD/MIN –671**

**[P R I C E P A R T]**

Schedule of Quantity for: **“Repairing of Bituminous road at Turamdih Township.”**

**(Re-Tender) to N. I. T No. TMD/MIN - 671**

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
1	Providing and laying bituminous macadam of thickness 75 mm as per site condition laid in proper grade and camber & superelevation, mixing homogeniously and compacted in layers by power road roller of capacity minimum 8-10 T as per specification including heating bitumen to required temperature finishing the surface complete job as per MOST specification and direction of Engineer-in-charge including cost of all labour equipments tools and tackles but excluding cost of stone aggregate and bitumen only. (Net quantity of stack measurement of stone aggregate after deduction of prescribed percentage of voids measured against item No. 6 will be considered for payment against this item	<b>5700.00</b>	<b>Sqm</b>			
2	Providing & applying tack coat using hot straight run bitumen of grade 80/100 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications on W.B.M @ 0.75 Kg/sqm	<b>11400.00</b>	<b>Sqm</b>			

**(Re-Tender) to N. I. T No. TMD/MIN - 671**

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
3	Providing and laying premix carpet surfacing of thickness 25 mm as per site condition laid in proper grade and chamber & superelevation mixing homogenously and compacted in layers by power road roller of capacity minimum 8-10 T as per specification including heating bitumen to required temperature finishing the surface complete job as per MOST specification and direction of engineer-in-charge including cost of all labour, equipments tools and tackles but excluding cost of stone aggregate and bitumen only.	<b>5700.00</b>	<b>Sqm</b>			
4	Providing and laying premixed sand seal coat over hot premix carpet surfacing as per site condition laid in proper grade and camber & super elevation, mixing homiginiously and compacted in layers by power road roller of capacity minimum 8-10 T as per specification including heating bitumen to required temperature finishing the surface complete job spreading sand / stone dust over finished surface as per MOST specification and direction of engineer-in-charge including cost of all labour, equipments tools and tackles but excluding cost of bitumen only.	<b>5700.00</b>	<b>Sqm</b>			
5	Surface dressing of the ground/road berms in proper grade and chamber including removing vegetation and in equalities not exceeding 15cm deep and disposal of rubbish lead upto 50 mtr as per direction of EIC	<b>3000.00</b>	<b>Sqm</b>			

**(Re-Tender) to N. I. T No. TMD/MIN - 671**

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
6	Supplying and stacking at site a) ¾ or 53mm to 22.4mm size stone aggregate	<b>300.00</b>	<b>CUM</b>			
	b) Stone screening 11.2mm nominal size	<b>150.00</b>	<b>CUM</b>			
7	For items not covered under above schedule of quantities mentioned Sl. No. 1 to 6, but covered under CPWD DSR - 2007, quoted	% above/below than DSR - 2007 Rates				
	Total					
	Rebate if any (_____)				%	
	<b>Grand Total</b>					

**Grand Total in words .....**

**NOTE:**

1. All items rates must be written in figures and words without which tenders are liable to be rejected.
2. All the pages of tender document must be duly signed by tenderer along with their seal.
3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered.
4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice, hence tenderer are advice to quote their rates as per N. I. T conditions.
5. The Quoted rate should be inclusive of all taxes and duties including Service Tax

Signature with Seal