

URANIUM CORPORATION OF INDIA LIMITED
MOHULDIH MINE

UCIL/MHD/ELECT/227/2019

Date:- 01.08.2019

**Sub:-Quotation against erection & commissioning of spike type lightening
arrester at Arch room (Mohuldih mine)**

Dear Sir,

Sealed quotations are invited for the above job in the prescribed format given below within 7days.You are requested to submit the sealed quotation before 09.08.2019 up to 5PM in the office of Addl.Supdt.(Elect.),Mohuldih at Mohuldih mine.(Post-Dudra,Dist-Saraikla kharsawn,Jharkhand-831002)

S.K.Chakraborty
Addl.Supdt.Elect.Mohuldih
Mob:- 9852609058

Shedule for Erection & commissioning of spike type lightening arrester at Arch room (Mohuldih mine)

S.No	Item description	Unit	Qty	Rate in Rs.	Rate in words	Total amount in Rs.
1	Supply of 11.5mtrs long M.S. tubular pole.	Nos	2			
2	Pit digging for grouting of tubular pole ,Depth-1950mm X Width 900mm X 900mm.	Nos	2			
3	Erection of tubular pole of length 11.5 mtrs long, all material including cement will be supplied by contractor.Erection of pole on ratio 1:2:4	Nos	2			
4	Preparing of earth pits with supply of all materials including 03mtrs long, 3.64mm thick perforated G.I. tube with alternate layers of salt and charcoal. The earth pits shall have bricks chamber at the top with chequered plate (6mm thick) with lifting arrangements.Earthpit as per IS-3043 with latest arrangements.	Nos	2			
5	Supply & fixing of G.I. pipes 1.5m long X15mm 91/2" bore (class-B) air terminals having 7.5cm(3") dia6mm (4") thick GI flange at the bottom end & 5 discharged rod.	Nos	4			
6	Supply & laying of 25X3mm GI strips underground (500mm)below ground including earth excavation, back filling.	Mtrs	100			
7	Supply & laying of 2X6 SWG G.I. wire along the wall clamping(including supply of clamp, nut & bolts etc)	Mtrs	25			
8	Supply & fixing of pin insulator, grade-1.1KV	Nos	50			

S.No	Item description	Unit	Qty	Rate in Rs.	Rate in words	Total amount in Rs.
9	Fabrication job. Required manpower(1 Skilled X 2days + 1 Unskilled X 2days)	Skilled	1No X 2days			
		Unskilled	1No X 2days			
10	Concrete road cutting (approx. 5mtrs) Required manpower(4 Unskilled X 2days)	Unskilled	4No X 2days			

Total Rs.
Add GST @ 18% :-
Total after add GST Rs.

Total in words:-