

Schedule of Quantity for: “Jungle cleaning & garden maintenance work at Mohuldih Mines.”

N. I. T No.: MHD/CIV – 100

[P R I C E P A R T]

Schedule of Quantity for: “Jungle cleaning & garden maintenance work at Mohuldih Mines

N. I. T No. MHD/CIV - 100

Part "A" – Schedule of Quantity for Jungle cleaning

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. All kinds of soil including all material, labour, tools & tackles etc complete as per the direction of EIC.	1000.00	Sqm			
2	Clearing jungle with petrol operated jungle cutting by machine / labour including providing of labours/ operator / fuel and maintenance of machine and removal of rubbish upto a distance of 2.0KM outside the periphery of the area cleared.	125000.00	Sqm			
3	Felling trees of the girth (measured at a height of 1m above ground level) including cutting of trunks and branches removing the roots and stacking of serviceable material and disposal of unserviceable material beyond 30cm girth upto and including 60cm girth	128.00	Each			

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
4	Deployment of one unskilled labour for Regular maintenance of lawns for twelve months including uprooting of unwanted grass and weeds, mowing of lawns by lawn mover once in a month watering, applying fertilizer and pesticides including cost of tools, tackles and labour complete as per instruction of Engineer-in-charge. (Fertilizers and pesticides will be supplied by deptt free of cost).	300.00	Man days			
	Total of Part "A"					

Part "B" – Schedule of Quantity for Garden Maintenance

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
5	Regular maintenance of lawns for twelve months, watering, applying fertilizer and pesticides including cost of tools, tackles and labour complete as per instructions of Engineer-in-charge. (Fertilizers and pesticides will be supplied by deptt free of cost).	7500.00	Sqm			
6	Regular maintenance of ornamental plants including pot plants for twelve months removing of unwanted grass, weeds, turning of soil, around the plants, making Thelma, sticking support if needed, watering applying of pesticides and fertilizers etc including cost of all labour, tools and tackles complete as per instruction of Engineer-in-charge. (Fertilizers and pesticides will be supplied by deptt free of cost).	250.00	Each			
7	Regular maintenance of hedge plants for twelve months including watering, cutting, dressing, cleaning etc and disposal of rubbish upto a lead of 50 mtrs. Including cost of all labour, tools, tackles etc. complete as per specifications and directed by Engineer-in-charge.	90.00	RM			
	Total of Part "B"					
	Total of Part "A" + Part "B"					
	Rebate if any in words (_____)				%	
	Grand Total of Part "A" + Part "B"					

Grand Total in words _____

Note:-

1. All items rates must be written in figures and words without which tenders are liable to be rejected.
2. All the pages of tender document must be duly signed by tenderer along with their seal.
3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered.
4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice, hence tenderer are advice to quote their rates as per N. I. T conditions.
5. The quoted rate should be inclusive of all taxes and duties including Service Tax

Signature with seal