

Schedule of Quantity for: **“Laying of Industrial water pipeline at Turamdih Mines”**

N. I. T No.: TMD/MIN – 657

[P R I C E P A R T]

Schedule of Quantity for: Laying of Industrial water pipeline at Turamdih Mines

N. I. T No. TMD/MIN - 657

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount
1	Earth work in excavation over areas (exceeding 30cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m disposed earth to be levelled and neatly dressed in all kinds of soil other works except pipe line works.	120.00	CUM			
2	Taking delivery of PVC/G. I pipe transport and laying including refilling jointing etc complete with all fittings works and as per direction of Engineer-in-charge but excluding the cost of PVC / G. I pipe. 100mm dia nominal bore	1100.00	RM			
3	Taking delivery of G. I pipes transport and laying including jointing, bend, Tee, Flange, socket, Tee with Gasket joint etc complete with all fittings works and as per direction of Engineer-in-charge. But excluding the cost of G. I pipes. a) 50mm dia nominal bore	100.00	RM			
	b) 150mm dia nominal bore	500.00	RM			

4	Providing and fixing G. I Union in existing GI pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required or as per the direction of Engineer-in-charge. a) 50 mm nominal bore	10.00	Nos.			
	b) 100mm dia nominal bore	5.00	Nos.			
	c) 150mm dia nominal bore	15.00	Nos.			
5	Painting of G. I pipes & fittings with two coats of anti-corrosive bitumastic paint of approved quality and as per the direction of Engineer-in-charge. a) 50 mm nominal bore	100.00	CUM			
	b) 100mm dia nominal bore	100.00	Cum			
	c) 150mm dia nominal bore	500.00	Sqm			

6	Providing and filling sand of grading zone V or coarser grade all round in GI pipes in external work as per the direction of Engineer-in-charge.a) 50 mm nominal bore	500.00	RM			
	b) 100mm dia nominal bore	100.00	RM			
	c) 150mm dia nominal bore	500.00	RM			
7	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) Make: NETA/LEADER/KIRLOSKAR / L&T/ AUDCO a) 50 mm nominal bore	16.00	Nos.			
	b) 100mm dia nominal bore	1.00	No.			
	c) 150mm dia nominal bore	1.00	No.			

Total

Rebate if any in words (_____)

%

Grand Total

Grand Total in words (_____)

Note:-

1. All items rates must be written in figures and words in case of any discrepancies arises in the rate written in words & figures then rate written in words shall be considered.
2. All the pages of tender document must be duly signed by tenderer along with their seal.
3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered.
4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice. Tenderer are advice to quote their rates as per N. I. T & tender conditions.
5. The quoted rate should be inclusive of all taxes and duties including Service Tax

Signature with seal