

URANIUM CORPORATION OF INDIA LIMITED
JADUGUDA

Ref: UCIL/Mill/309/600/2022

October 11, 2022

Enquiry

To:

1) M/s. Bhagwati Enterprises

Village: - Durku

P.O.:- Rakhamines

Dist:- Singhbhum (East)

JHARKHAND - 832 106

2) M/s. General Electrical Works

Badia Road No. – 3

P.O. :- Mosaboni Mines

Dist. :- East Singhbhum

Jharkhand - 832 104

3) M/s. Singson Electrical

In front of Apana Aangan

Sai Mandir Road

Ghorabandha, Telco Colony

Jamshedpur – 831008

Jharkhand

Sub: **Repairing of rotor assy. for 25HP & 20HP, 6pole squirrel cage induction motor of GEC make installed in belt conveyer at Jaduguda Mill.**

Sealed quotation(s) is/are invited as per the price bid format attached alongside for the above mentioned job. Sealed quotation may be reached to the office of the undersigned on or before 19.10.2022.

Special Terms and Conditions

1. Completion Time: -

- a) Complete repairing and delivery of total 05 nos. rotors assy of 25 Hp & 20 HP GEC motor to UCIL has to be done within 90 working days from the date of receipt of motors through returnable gate pass.
- b) Total 05 (Five) Nos. of defective rotors are to be repaired by contractor at his works, whereas 02 (Two) Nos. of rotors are to be repaired in the 1st phase followed by handing over of repaired rotor to UCIL. Another 03 (Three) Nos. rotors shall be received by the contractor in the 2nd phase followed by handing over of repaired rotor to UCIL. All the rotor assy shall be taken out through returnable gatepass provided by UCIL.

2. **Security Money Deposit :-**
Security Deposit equivalent to 03 (Three) % of the ordered value is required to be deposited in Accounts Department-UCIL in the form of demand draft before the commencement of the work. 100% security deposit will be refunded on written request in duplicate to the Engineer-in-charge after satisfactory completion of defect liability period of 06 (Six) Months.
3. **Payment Terms: -** The Contractor has to hand over of repaired rotor assy within stipulated time. After receipt of repaired rotor assy at our works, it will be fitted with of motor from our end and trail will be processed at our works. Final Bill will be paid after successful trail of rotor assy at our works.
4. **Rate: -** Rate of the individual rotor shall be furnished with supply of all rewinded materials required to complete the job with GST after deducting the scrap copper value. The rate quoted by the contractor shall be firm. No escalation will be entertained after quoted price.
5. **Defect liability period:-**
A defect liability period of 06 (Six) months from date of commissioning after receipt of repaired rotor at site. Further, the contractor will be responsible for rectifying the defect at his own cost if rotor fails under defect liability period.
6. **Bank Guarantee :-**
10 (Ten) % of work order value has to be submitted as bank guarantee/security deposit in favour of UCIL, Jaduguda payable at SBI, Jaduguda for taking out the defective rotor from UCIL premises & the B.G. will be returned immediately after handing over of repaired rotor at our UCIL site after submitting application by the party.
7. **Transportation :-**
The packing & to and fro transportation of defective / repaired rotor from UCIL Jaduguda (Mill) and back shall be arranged by the contractor at his own cost. Any damage to the rotor during transportation to/from UCIL shall be assessed in contractor's account.
8. **Penalty :-**
 - i) Failure in no load testing / load testing of rotor shall be rectified by contractor at his own cost. If the motor is found to be defective in any manner due to poor workmanship in winding or any mechanical damage to the rotor.
 - ii) If the rotor is not repaired within the completion period then ½ (Half) % per week will be levied and maximum upto 05 (Five) % of the contract value for a delay upto ten weeks from completion period. The order will be cancelled if the party fails to complete the work even after 10 (Ten) weeks from completion period.
9. **Indemnity Bond: -**
An indemnity bond shall be submitted by you against any loss/damage of rotor in your custody.

SCOPE OF WORK

- 1) The job shall be carried out in contractor's work in phase wise, after shifting of total 05 (Five) Nos. (02 Nos. in 1st phase & 03 Nos. in 2nd Phase) rotor assy from UCIL Mill to contractor's works by his own transport through returnable gate pass of UCIL permitted by competent authority.

Yours truly
For Uranium Corporation of India Limited

(Ramesh Besra)
Chief Supdt. (Elect.) Mill

Schedule of Item(s) & Rate(s)

Sub: Repairing of rotor assay for 25 HP & 20 HP, 6 pole squirrel cage induction motor of GEC make installed in belt conveyor at Jaduguda Mill

Enquiry No. : Ref: UCIL/Mill/309/600/2022 dated: 11/10/2022

Sl. No.	Description	Qty.	Rate/Unit (Rs.)		Amount (Rs.)	
			(in figures)	(in words)	(in figures)	(in words)
1.	Dismantling of rotor strip from rotor and cleaning of rotor slots.	05				
2.	Supply and installation of new copper strip with proper size, length, angle and brazing with 18 % silver mix brazing rod. Brazing of copper strip to copper ring and varnishing of complete rotor core.	05				
3.	Dynamic balancing of newly fitted rotor.	05				
4.	Transporting of rotor to and fro from UCIL to our workshop.	05				
5.	Total					
6.	GST @ 18 %					
7.	Grand Total after GST					

(Signature & seal of contractor)

